



307 E. 39<sup>th</sup> Street  
South Sioux City, NE 68776  
P- (402) 412-3550  
F- (402) 412-3552  
nherbst@hnrco.com

---

**Bidders Clarification #2 – 4/2/2015**

**Flagstaff Subaru**

**General Comments:**

- “Final” civil drawings will be issued on Monday April 6<sup>th</sup>. As a result the **Bid Date and time for the following work scopes will be adjusted to Thursday April 9<sup>th</sup> at 3:00 p.m. (your time).**
  - **Earthwork, site utilities, paving, curb and gutter.**
- **All other bids are due Monday April 6<sup>th</sup>, by 3:00 p.m. (your time).**

**Drawing and Bid Clarifications:**

- The carwash equipment room on sheet A111 and structural sheet S101 and S201 extends up and over the pre-cast plank.
- The Janitors closet 130 and Riser room 131 masonry bears on top of the pre-cast plank.

**Roofers Scope of Work:**

- Your base bid should be a four ply built up asphalt roof system over poly iso insulation. Please disregard the “base” bid scope in the instructions to bidders. I should have been changed to reflect the plans. Please note your warranty for the four ply system on your proposals.
- The alternate price for a 60 mill fully adhered roof system remains the same.

**Site Work:**

- The dirt work contractor will be responsible for backfilling behind back of curb. Backfill may be completed with on site materials. Leave the backfill down 3” from top of curb for the landscaper.
- Disregard any mention of topsoil for planting beds. The landscaper will treat the beds as necessary.

End of Section